



Republic of the Philippines
UNIVERSITY OF RIZAL SYSTEM
Province of Rizal

Cp No. (63)918-9519618
urs.bacsecretariat2020@gmail.com

Date : October 23, 2025

Company/Supplier Name : _____

Address : _____

Please quote your lowest price on the item/s listed below, subject to the General Conditions on the last page, stating the shortest time of delivery and submit your sealed quotation duly signed by your representative not later than 10/27/25 to URS SPMO, Morong Rizal.

ARIEL M. PLANTILLA, DBA
Chairperson, BAC

- NOTE: 1. ALL ENTRIES MUST BE TYPEWRITTEN
2. DELIVERY PERIOD WITHIN 90 CALENDAR DAYS
3. WARRANTY SHALL BE FOR A PERIOD OF SIX (6) MONTHS FOR SUPPLIES & MATERIALS, ONE (1) YEAR FOR EQUIPMENT, FROM DATE OF ACCEPTANCE BY THE ENTITY
4. PRICE VALIDITY SHALL BE FOR A PERIOD OF 45 CALENDAR DAYS
5. G-EPS REGISTRATION CERTIFICATE SHALL BE ATTACHED UPON SUBMISSION OF THE QUOTATION
6. BIDDERS SHALL SUBMIT ORIGINAL BROCHURES SHOWING CERTIFICATIONS OF THE PRODUCT BEING OFFERED

ITEM NO.	ITEM & DESCRIPTION	QTY.	UNIT	BID PRICE	TOTAL BID PRICE
1	Construction of guard house located at main gate	1	lot(s)		
	nothing follows				
	-				
	LOT ABC - Php 400,000.00				
	-				

Brand and Model : _____

Delivery Period : _____

Warranty : _____

Price Validity : _____

After having carefully read and accepted your General Condition, I/We quote you on the items at prices noted above.

CERTIFICATION

I hereby certify that I have personally conducted this canvass and that the price(s) quoted is/are true & correct and the signature of the representative of the company who submitted the quotation(s) is/are genuine.

POSTED TO PHILGEPS

Printed Name & Signature of Authorized Canvasser

Printed Name / Signature

Tel. No. / Cell phone No.

E-mail address

Date

Tin Number

URS-AF-AS-PRO-F-2017-02

Rev. 00

Effectivity Date August 15, 2017

Modified version of RFQ form
(SF-GOOD-60, May 2004)

RFQ-2025-10-0812
PR-2025-01-0210
END USER: NAMEROD F. MATEO, PH. D.

Note: Mandatory documents
*Delivery Receipt w/ ATP Number
*Service/Billing/Sales Invoice
*Official/Collection Receipt
*Philgeps registered atleast RED membership
(Above 50k)
*Mayor's Permit
*Tax Clearance/ BIR 2303
*DTI Certificate

Republic of the Philippines
UNIVERSITY OF RIZAL SYSTEM
Province of Rizal

University Project Management Unit

CONSTRUCTION OF GUARD HOUSE AT MAIN GATE-URS TANAY CAMPUS								
Tanay Campus								
DETAILED ESTIMATE								
ITEM	WORK DESCRIPTION	QTY	UNIT	UNIT COST (P)		COST		TOTAL (P)
				MATERIAL	LABOR	MATERIAL	LABOR	
I.	CLEARING AND GRUBBING							
	Clearing and Grubbing	12.24	m ²					
	Layout and Staking	12.24	m ²					
II	EXCAVATION							
	Structure Excavation	6.40	m ³					
	Backfill	3.84	m ³					
III.	REINFORCED CONCRETE							
	Column Footing, Cast In Place	0.62	m ³					
	Cement	5.57	bag					
	White Sand	0.31	m ³					
	Gravel, 3/4"	0.62	m ³					
	Wall Footing	1.69	m ³					
	Cement	15.17	bag					
	White Sand	0.84	m ³					
	Gravel, 3/4"	1.69	m ³					
	Column	0.63	m ³					
	Cement	5.70	bag					
	White Sand	0.32	m ³					
	Gravel, 3/4"	0.63	m ³					
	Slab on Grade	1.68	m ³					
	Cement	15.15	bag					
	White Sand	0.84	m ³					
	Gravel, 3/4"	1.68	m ³					
	Lintel Beam	0.21	m ³					
	Cement	1.85	bag					
	White Sand	0.10	m ³					
	Gravel, 3/4"	0.21	m ³					
IV.	REINFORCING STEEL							
	Column Footing							
	12mmØx6.0m Deformed Bar	31.97	kg					
	G.I. Tie Wire #16	1.38	kg					
	Wall Footing							
	12mmØx6.0m Deformed Bar	73.53	kg					
	10mmØx6.0m Deformed Bar	13.62	kg					
	G.I. Tie Wire #16	1.88	kg					
	Column							
	12mmØx6.0m Deformed Bar	45.47	kg					
	10mmØx6.0m Deformed Bar	81.40	kg					
	G.I. Tie Wire #16	4.75	kg					
	Slab on Grade							
	10mmØx6.0m Deformed Bar	44.40	kg					
	G.I. Tie Wire #16	5.80	kg					
	Lintel Beam	49.00	bag					
	12mmØx6.0m Deformed Bar	10.66	kg					
	10mmØx6.0m Deformed Bar	5.33	kg					
	G.I. Tie Wire #16	10.54	kg					
V.	MASONRY WORKS							
	Exterior Wall	38.57	m ²					
	CHB 5", Ordinary	483.00	pc					
	Cement, 40kg bag	40.00	bag					
	White Sand	3.26	m ³					
	12mmØx6.0m Deformed Bar	72.96	kg					
	10mmØx6.0m Deformed Bar	51.08	kg					
	Interior Wall	9.83	m ²					
	CHB 5", Ordinary	123.00	pc					
	Cement, 40kg bag	11.00	bag					
	White Sand	0.83	m ³					
	12mmØx6.0m Deformed Bar	18.60	kg					
	10mmØx6.0m Deformed Bar	13.02	kg					

	<i>Interior Wall</i>	3.64	m ²					
	CHB 4", Ordinary	46.00	pc					
	Cement, 40kg bag	4.00	bag					
	White Sand	1.59	m ³					
	12mmØx6.0m Deformed Bar	6.89	kg					
	10mmØx6.0m Deformed Bar	4.83	kg					
	<i>Septic Tank</i>	1.00	lot					
	CHB Laying and Plastering	1.00	lot					
	<i>Plastering Works, Class "B" Mixture @ 20mm thk</i>	69.07	m ²					
	Cement, 40kg bag	17.00	bag					
	White Sand	1.38	cum					
VI.	FALSEWORKS AND FORMWORKS							
	<i>Column and Beam</i>							
	Coco Lumber 2x3x10'	25.00	pc					
	Phenolic Board, 4'x8'	4.00	pc					
	Common Wire Nail, 2-1/2"	5.00	kg					
	Common Wire Nail, 1"	2.00	kg					
VII.	METAL STRUCTURES							
	<i>Stiffener Beam-Metal</i>							
	50mmx50mmx6mm Angle Bar	8.00	pc					
	<i>Roof Framing</i>							
	50mmx50mmx6mm Angle Bar	5.00	pc					
	38mmx38mmx4.5mm Angle bar	6.00	pc					
	10mm Sagrod	1.00	pc					
	50x150mmx1.5mm C-Purlins	6.00	pc					
	Dyna Bolt, 16mm	16.00	pc					
	Fascia Board, 12"x1/2"x2.4m	6.00	pc					
	Hardiflex Screw, 1-1/2"	150.00	pc					
	Metal Washer	32.00	pc					
	Lock nut, 10mm	32.00	pc					
	Consumables							
	Welding Rod	8.00	pc					
	Cutting Disc, 4"	3.00	pc					
VIII.	PRE-PAINTED METAL SHEETS							
	<i>Pre-painted Metal Sheets</i>							
	Rib type Roofing, 0.5mm thk	31.56	l.m.					
	Roof Flashing	1.00	pc					
	Roof Insulation, Single Sided Foil 10mm	32.00	l.m.					
	Consumables							
	Drill Bit	2.00	pc					
	Tekscrew	150.00	pc					
	Sealant	1.00	tube					
VII.	CARPENTRY AND JOINERY WORKS							
	<i>Ceiling</i>							
	Carrying Channel, 12mmx38mmx5.0m	5.00	pc					
	Metal Furring, Double, 19mmx50mmx5.0m (spaced @0.60m)	7.00	pc					
	Wall Angle, 25mmx25mmx3.0m	13.00	pc					
	W-Clip	12.00	pc					
	Blind Rivets, 5/32x1/2	60.00	pc					
	Hardiflex Screw, 1"	272.00	pc					
	Fiber Cement Board, 4'x8'x3.5mm	6.00	pc					
VIII.	TILING WORKS							
	<i>Floor Tiles</i>							
	Non-Skid Tile, 30cmx30cm	41.00	pc					
	Tile Adhesive, 25kg bag	3.00	bag					
	Tile Grout, 2kg per bag	1.00	bag					
IX.	DOORS AND WINDOWS							
	<i>Doors</i>							
	PVC Door, 0.60mx2.10m with jamb incl accessories	1.00	set					
	<i>Windows</i>							
	0.80x1.20m 1/4" thk Clear Glass in Aluminum(Awning) frame	1.00	set					
	0.40x0.40m x1/4" th Clear Glass in Aluminum(Awning) Frame	1.00	set					
	Consumables							
	Sealant	1.00	lot					
IX.	PAINTING, VARNISHING AND OTHER RELATED WORKS							

	Exterior and Interior Wall							
	Mesh Tape	1.00	roll					
	Skimcoat, Zemcoat	5.00	bag					
	Sandpaper # 120	10.00	sheet					
	Sandpaper #150	10.00	sheet					
	Elastomeric Paint ROS or approved equal	2.00	gal					
	Flat latex B-701, Boysen or approved equal	1.00	pail					
	Semi-Gloss Latex, B-715, Boysen or approved equal	1.00	gal					
	Paint Brush 4"	1.00	pc					
	Baby Roller, Cotton	1.00	pc					
	Rugs, Cotton	1.00	kg					
	Epoxy Primer (for metal)	1.00	liter					
	Epoxy Enamel (for metal)	1.00	liter					
	Rust Converter (for metal)	1.00	liter					
X.	PLUMBING WORKS							
	<i>Sewerline and Sanitary Line</i>							
	3" diamter UpvC Plumbing Pipe(NELTEX)	2.00	pc.					
	2" diameter UpvC Plumbing Pipe(NELTEX)	1.00	pc.					
	3" diamter UpvC 90 deg Elbow(NELTEX)	1.00	pc.					
	2" diamter UpvC 90 deg Elbow(NELTEX)	1.00	pc.					
	3" diamter UpvC Tee (NELTEX)	1.00	pc.					
	2" diameter UpvC Tee (NELTEX)	1.00	pc.					
	Wye Reducer 3"x 2 " (NELTEX)	1.00	pc.					
	PVC solvent cement 400cc (NELTEX)	1.00	can					
	<i>Cold Water Line</i>							
	1/2" diameter PPR Pipe(PN10)(NELTEX BRAND)	4.00	length					
	1/2" diameter PPR 90 deg Elbow	8.00	pc.					
	1/2" diameter PPR Tee	1.00	pc.					
	1/2" diamter PPR female adaptor	2.00	pc.					
	1/2" diamter PPR male adaptor	2.00	pc.					
	1/2" diameter Elbow Female adaptor	2.00	pc.					
	1/2 " diamter Check Valve	1.00	pc.					
	1/2" diamter PPR Gate Valve	2.00	pc.					
	Eco Tech Water Meter DN 15(1/2") with fittings	1.00	assy					
	Teflon tape	2.00	pc.					
	Plumbing Fixtures							
	Water Closet (Pozzi)	1.00	pc.					
	Faucet(Pozzi)	1.00	pc.					
	4 inch diameter Floor Drain(Sefa)	1.00	pc.					
XI.	ELECTRICAL & ELECTRONIC WORKS							
	<i>Electrical System</i>							
	(AMERICA) Panel Board Plug in Type 4 branches	1.00	pc.					
	PVC Pipe electrical, 20mmdia.	15.00	length					
	5.5mm2 THHN Wire	100.00	m					
	3.5mm2 THHN Wire	60.00	m					
	(Omni) 4"x4" Junction Box with cover	5.00	pc					
	(Omni) 2"x4" Utility Box with Cover	10.00	pc					
	(Omni) Duplex Universal Outlet with ground 16A	5.00	pc					
	(Omni) Single Convenience Outlet with Ground Classc Plate	1.00	pc					
	(Omni) LED Slim Panel Light 18 watts	2.00	pc					
	(Omni) LED Recessed Circular Downlight 10 watts	6.00	pc					
	(Omni) 2 gang, 1-way switch in Classic Plate(P2-S13)	2.00	pc					
	(Omni) 1 gang, 1- way switch in Classic Plate(P1- S13)	1.00	pc					
	(Omni) Swivel Head Automatic Emergency Light AEL-390	1.00	pc					
	<i>CCTV System</i>							
	Dahua CCTV DVR 4 chanel H.265+/H.265 with I TB Hard disk and AC/dc adaptor	0.00	pc					
	Dahua Full Color Network Camera Smart H.265+ IP Cam 4MP	0.00	pc					
	CCTV Male and Female DC 12 V jack connector	6.00	pair					
	CCTV Video Balun 1080P	6.00	pair					
	Metal 4"x4" Junction Box with cover	4.00	pc					
	Metal 4"x4" Squre box with cover	4.00	pc					
	(PHILPLEX) UTP CAT 6 4 pairs 550MHz	20.00	m					
	CCTV Monitor 1080P 75Hz HD 24 inch	1.00	pc					
	Consumables							
	Electrical Tape, PVC Solvent Cement, Clamps, hangers	1.00	lot					

A TOTAL DIRECT COST
B OCM 15.00%
C PROFIT 10.00%
D VAT 5%(A+B+C)
E TOTAL COST A+B+C+D